

Knipstein/Conner Enterprises

10 Swamscott Street
Newfields, NH 03856
603-772-5288

Estimate

Number: E301

Date: August 07, 2023

Bill To:

Town of Kensington
95 Amesbury Rd
Kensington N.H.
03833

Ship To:

Kensington Highway Dept
Summer Maint

PO Number	Terms	Sales Rep
Summer Maint	upon receipt	Brian Knipstein

Date	Description	Amount
8/7/2023	Estimate to Install a new 24 ADS Culvert on Osgood Road. Pipe to be supplied by Town of Kensington Highway Dept. Scope of work to include. Saw cut existing pavement and Hual of site. Excavate for 24inch culvert. Place 6inches of stone under culvert. Backfill pipe with 3/4 stone and compact. Place fill and compact to 16inches below existing pavement. Place and compact 12inches of crush gravel. Grade for 4inches of pavement patch. place 4inches of patch pavement. Total Estimate.	7,950.00

Culvert placement will be at the direction of the Kensington Highway Manager. Thank you Brian Knipstein.

Total	\$7,950.00
--------------	-------------------

Matt

MATRIX

INVOICE/CONTRACT

PAVING & EXCAVATION, INC.

Paul (603) 394-0701

P.O. Box 796, Seabrook, NH 03874

FREE ESTIMATES • INSURED • LICENSED

PROPOSAL SUBMITTED TO:

Town Kensington

STREET

CITY, STATE, ZIP

ARCHITECT

DATE OF PLANS

PHONE

JOB NAME

JOB LOCATION

JOB PHONE

Page No. of Pages

DATE: 8/8/2023

Install Drainage

Osgood Rd

We hereby propose to furnish materials and labor necessary for the completion of:

- Saw cut hot top pavement
- Disposal hot top
- Excavate next to existing culvit
- Install proposed culvit "Supply by others"
- Backfill with proper materials
- Compaction ground and top of pipe
- Install 12 inches of gravel under pavement
- Install 3 inches of Hot Top on disturbed areas
- Install head walls with stone and rip rap
- 6 inch minus
- Clean up job

labor and materials — \$6,545.00

WE PROPOSE hereby to furnish material and labor - complete in accordance with above specifications, for the sum of:

Six thousand five hundred forty five — dollars (\$ 6,545.00)

Payment to be made as follows:

All material is guaranteed to be as specified. All work to be completed in a substantial workmanlike manner according to specifications submitted, per standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our works are fully covered by Workmen's Compensation Insurance.

Authorized Signature

R.E.M.

Note: This proposal may be withdrawn by us if not accepted within _____ days.

ACCEPTANCE OF PROPOSAL The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature

Handwritten signature and date: approved 8/21/23